

Suros Logic Systems, LLC

123 Main Street Clearwater FL, 33767
123-456-7890
support@suroslogic.com

Invoice Date
2026-01-01

INVOICE #SLS-2026-182
"Systems That Work Smarter."

CLIENT
Bob Smith
889 South Shore, Clearwater FL 33767
(777) 090-0000
customer@email.com

SALESPERSON	JOB	PAYMENT TERMS	WORKING WEEKS
John Doe	Kitchen Remodel – 889 South Shore	50% deposit required before work begins. Weekly progress payments due every Friday. Final amount due upon project completion.	4 weeks

Description

#	Scope	Line Total
1	<p><u>Plumbing</u></p> <p><i>Material & Labor Included: Yes</i></p> <ul style="list-style-type: none">- Disconnect existing plumbing fixtures and cap supply lines as required.- Install new PEX water lines, making all necessary connections and pressure testing before closing walls.- Replace the existing garbage disposal, connect to plumbing, and test for leaks and functionality.- Install new shutoff valves for kitchen fixtures, ensuring all connections are leak-free.	\$3,300.00
2	<p><u>Drywall</u></p> <p><i>Material & Labor Included: Yes</i></p> <ul style="list-style-type: none">- Remove damaged drywall in the kitchen and haul debris off site.- Install new 1/2" drywall, tape joints and corners, and apply multiple coats of joint compound.- Sand between coats as needed and leave walls ready for primer and paint.	\$2,500.00
3	<p><u>Electrical</u></p> <p><i>Material & Labor Included: Yes</i></p> <ul style="list-style-type: none">- Install recessed lighting fixtures as per layout and connect to existing wiring.- Install two new GFCI outlets in the kitchen and test for proper function and safety.- Replace kitchen circuit breaker with an upgraded model and ensure circuits are properly connected and labeled.	\$4,700.00

4	Flooring <i>Material & Labor Included: Yes</i> - Remove existing tile flooring and dispose of all debris off site. - Lay new LVP flooring throughout the kitchen, ensuring a secure and even installation. - Install new baseboards to match existing trim, scribing to walls as necessary and caulking edges.	\$5,400.00
5	Demolition <i>Material & Labor Included: Yes</i> - Carefully remove existing cabinetry and disconnect all associated plumbing and electrical. - Remove countertops and all associated fixtures, leaving surfaces clear. - Clear and dispose of resulting debris off site, leaving the area ready for new installations.	\$1,500.00
6	Countertops <i>Material & Labor Included: Yes</i> - Create precise templates for new quartz slabs, ensuring accurate cutting and fitting. - Install quartz countertops and secure properly, checking for appropriate overhang and stability. - Apply sealant to stone surfaces and secure with a quality finish for longevity.	\$4,200.00
Subtotal		\$21,600.00

Contingency Coverage (10%)	\$2,160.00
Covers miscellaneous materials and unexpected repairs.	

Tax (7%)	\$1,512.00
Total Cost	\$25,272.00
Deposit Required	\$12,636.00
Weekly Progress Payments × 4	\$3,159.00

THANK YOU FOR YOUR BUSINESS!